



## 3300-NK

Three gang electrical box for use with nonmetallic

sheathed cable

**Carton Quantity: 20** 

Mounting Description: Angled mid nails

Box Type: Wall - Switch/Receptacle

Box Features: Nails, Speed "K" nonmetallic clamps

**Installation Type:** New Work

Height: 3-3/4 in Width: 5-11/16 in Depth: 3 in Volume: 46 cu in Number of Gangs: 3

# **Product Info**

**Brand:** fiberglassBOX **UPC:** 85339141778 **UNSPSC:** 39121308

Carton Weight: 16 lbs Carton Length: 16 in Carton Width: 12 in Carton Height: 12 in

Country of Origin: United States of America

Color: Off white

Material: Fiberglass reinforced polyester

**Additional Materials:** Carbon steel fasteners, Polyvinyl

chloride clamps

#### Features:

Machine tapped device holes, offset gauge marks, leveling ribs, rigid hard box construction, no distortion with high temperatures, shatter resistant with low temperatures, Speed "K" Clamps factory installed

#### **Application:**

New work residential construction 2 HR fire resistive walls, UL approved for back-to-back installation

#### Standards:

ANSI / UL 514C: File No. E30594



## **Fire Classification:**

Fire Test of Building Construction Materials ANSI / UL 263: File No. CEYY.R9379 (Category / File No.)

Note: Products must also be certified to: ANSI / UL 514C

## Fire Resistance Classification in Wall Assemblies 2-Hours or less

Shall be separated by a horizontal distance of not less than 3 inches

Note: For more details please refer to the UL fire resistive directory and Allied Moulded's CEYY.9379 (Outlet boxes and fittings classified for fire resistance)